



POWER HOUSE

Complete Air System Pre-Built & Pre-Wired



VARI-AIR—POWERHOUSE





- Premanufactured shed with Blower mounted inside
- Galvanized Enclosure with a 4x7 tube iron and C-Channel floor.
- All items pre-wired—Bring in main power to one circuit breaker.
- All Vari-Air system controls mounted on exterior.
- Red=System Off / Green=System On Yard Lights.
- Maintenance Kit Included
- Warranty doubles from 2 to 4 years on blower, motor, and VFD.
- On-Site Start up with customer on all POWERHOUSE units
- Factory Designed, Assembled, Wired, and tested
- Complete Modular design for complete turn key system.



Vari-Air
2420 20th Ave S.
Moorhead, MN 56560

Ph. (218) 512-0438
www.vari-air.com
www.facebook.com/vari-air/



VFD/PSI CONTROL

- PSI Control is designed to increase motor speed when system pressure increases
- This system runs at the minimum speed required to deliver the corn to the bin, reducing damage.
- Our VFD/PSI control increases lifetime of blower, motor, piping, and other system parts.
- Single phase systems available up to 6" - 60 Hp

TRI-LOBE BLOWER

- Quiet operation due to lower operating RPM
- Tri-Lobe delivers more air than twin lobe design
- Blowers are re-packaged for agricultural conveying
- Blowers are PSI tested before shipment
- Also Included: Blower motor, Check valve, air filter, PSI gauge, Bypass valve, control air tubing, Blower oil
- 5 year warranty on blower




STANDARD AIR LOCK

- Air Lock brand new .004 clearance with feeler gauge
- After 1 Million Bushels through air lock re-check clearances—if over .012 air lock needs to be rebuilt
- Also Included: Air Lock stand, discharge hopper, 1Hp motor/gearbox, sprockets, guards, and testing.

PH STANDARD ACCESSORIES

- Pre-Filter tarp assembly
- Air Lock Centering Valve
- Start-Up Services
- Remote Air Box
- Maintenance Kit



Vari-Air
2420 20th Ave S
Moorhead, MN 56560



Ph. (218) 512-0438
www.vari-air.com
www.facebook.com/vari-air/